



**Williamson Park Project Cordova Recreation & Park District
Addendum #1 Issued on Friday November 4, 2022**

1. Some scope changes have occurred to this project. Please see revised plans and additional technical specifications on <https://crpd.com/resources-and-information/rfpsrfqs/> . Additional drip irrigation and shrub plantings have been added to the plans and the **installation of backflow and backflow enclosure has been removed.**
2. **The bid proposal form has been modified and can be found online at <https://crpd.com/resources-and-information/rfpsrfqs/>**
3. There are no sizes for the lateral lines shown on the irrigation plans.
All bubbler lateral lines shall be 1". All drip lines shall be 1" or 3/4" as shown on plan.
4. There is not manufacturer or model for the quick coupling valves on the irrigation legend.
The Quick Coupler shall be Rainbird 44LRC.
5. The drip tubing shown on the irrigation legend has 12" spacing. Please advise if this is the emitter spacing from each other on the tubing or is this to be installed at this spacing on center.
Drip tubing spacing shall ensure each plant has an emitter. Plant spacing is shown on plan.
6. There are no sizes shown for the remote control valves and gate valves. **Valve sizes shall be 2". The backflow installation and backflow enclosure installation has been removed from this scope of work.**
7. Please advise if valve #3 is a drip valve or remote control valve. Please identify this valve.
Valve number 3 is a remote control valve for drip irrigation.
8. Please confirm that the master valve and water meters are the same as shown on the plans. the symbols are different. **Master valve and water meter in legend are same as on plan.**
9. There is a quick coupling valve at the end of the lateral in the left corner of the irrigation plan. Please advise is this is a sprinkler. **The dark circles shown at the top left and right corners are actually property boundaries. Clarification has been made on the new irrigation plan.**
10. There is no sizing shown for the irrigation sleeves. Please advise.
Irrigation sleeves are existing and not in contract.

I have read and understand the above addendum.

Contractor Name:

Date:
